

BUSINESS AS USUAL WHILE PROBLEMS SOLVED BY CHANCE

Rubb's Restaurant *Lynchburg, VA*

The City of Lynchburg had issued a letter to the restaurant stating concerns with the settlement of soil along its rear and side walls. Further investigation revealed the block wall and concrete floor were cracked and repairs were needed. The foundation was stabilized with the A.B. CHANCE Helical System and repairs made - all while the restaurant continued "business as usual,"



CHANCETM
Since 1912
DOWN. RIGHT. SOLID.

PROJECT

Rubb's Restaurant

Lynchburg, Virginia

PRODUCT

- A.B. CHANCE SS5 piles with 10/12 in. helix configuration advanced an average of 21 feet

ADVANTAGES

- Quick installation of economical deep foundation
- Hydraulic installation with no vibration or spoils
- No disruption in daily business routine
- No excess noise

CONTRACTOR

- Custom Structures, Inc., Lynchburg, VA
Certified installer of A.B. CHANCE products

GENERAL CONTRACTOR

- Talbott Concrete and Construction

DESCRIPTION

- This project required installation of 5 A.B. CHANCE Helical Piles equipped with foundation underpinning brackets. Hydraulic jacks raised the underpinning brackets beneath the building's existing footing. Once the foundation was stabilized by the A.B. Chance Helical System, the wall and floor were repaired.

FOR MORE DETAILS ON THIS PROJECT, CONTACT WALDER FOUNDATION PRODUCTS
AT 804-798-3605 OR EMAIL: JHALL@WALDER.COM

WWW.WALDERFOUNDATIONPRODUCTS.COM

CALL JERRY HALL
TODAY AT
804-798-3605
TO SET UP A FREE
A.B. CHANCE LUNCH
SEMINAR FOR YOUR
FIRM.

WALDER FOUNDATION PRODUCTS

P.O. Box 1272

Ashland, VA 23005